Nutan Urja Solutions

A 703, Balaji Witefield, Near Sunni's World,

Sus Road, Sus, Pune 411 021

Phone: 83568 18381. Email: nutanurja.solutions@gmail.com

Date: 21/08/2019

CERTIFICATE

This is to certify that we have conducted Energy Audit at Brahma Valley College Of Engineering And Research Institute, Nashik as per the guidelines of Maharashtra Energy Development Agency (www.mahaurja.com) in the year 2018-19.

The College has already adopted Energy Efficient practices like:

- Usage of Energy Efficient LED Fittings
- Usage of Energy Efficient BEE STAR Rated equipment
- > Installation of Solar Thermal Hot Water System
- ➤ Installation of Solar PV street lights

We appreciate the support of Management, involvement of faculty members and students in the process of Energy Conservation & making the campus Green.

Nutan Urja Solutions,

K G Bhatwadekar,

18. Bhatulaka

Certified Energy Auditor,

EA - 22428

Report

On


Energy Audit

At

Brahma Valley College Of Engineering And Research Institute,

Nashik

(Year 2018-19)



Prepared by

Nutan Urja Solutions

A 703, Balaji Witefield, Near Sunni's World, Sus Road, Sus, Pune 411 021

Phone: 83568 18381. Email: nutanurja.solutions@gmail.com



Report


On

Energy Audit

At

Brahma Valley College Of Engineering And Research Institute, Nashik

(Year 2018-19)



Prepared by

Nutan Urja Solutions

A 703, Balaji Witefield, Near Sunni's World, Sus Road, Sus, Pune 411 021

Phone: 83568 18381. Email: <u>nutanurja.solutions@gmail.com</u>



Acknowledgement

We at Nutan Urja Solutions, Pune, express our sincere gratitude to the management of Brahma Valley College Of Engineering And Research Institute, Nashik for awarding us the assignment of Energy Audit of their college premises.

We are also thankful to various Head of Departments & other Staff members for helping us during the field measurements.

We hope that the recommendations stated in this report will be useful and worthy of discussions to take things forward to help implementation of energy conservation measures through energy savings. While we have made every attempt to adhere to high quality standards, in both data collection and analysis through the report, we would welcome your suggestions so as to improve upon this report further.



5. Recommendations

Table no 1: Recommendations for energy savings

| No | Recommendation | Annual Saving potential, kWh/Annum | Annual Monetary Gain, Rs. | Investment Required, Rs. | Payback period, |
|----|---|------------------------------------|---------------------------------|--------------------------------|-----------------|
| 1 | Replacement of 215 Nos T-8 fittings with 20W LED fittings | 4,300 | 47,300 | 137,815 | 35 |
| 2 | Replacement of 181 Nos Old Ceiling Fans with STAR rating fans | 2,353 | 25,883 | 393,494 | 182 |
| 3 | Installation of 100kW grid connected PV panel | 150,000 | 1,650,000 | 5,000,000 | 36 |
| | Total | 156,653 | 1,723,183 | 5,531,309 | 39 |

6. Notes & Assumptions

- 1. Daily working hours-10 Nos
- 2. Annual working Days-300 Nos
- 3. Average Rate of Electrical Energy: Rs 11/- per kWh



1. Introduction

Brahma Valley Educational Campus is located in the outskirts of Anjaneri, (Trimbakeshwar High-Way Nashik) comprising a sprawling campus of about 35 acres land. The campus is situated in the valley surrounded by hills & reflects the beauty of nature. This place is also known as the birth place of Lord Hanuman and is close to Trimbakeshwar Temple which is one of the 12 Jyotirlingas of Lord Shiva which adds to the holiness and beauty of this area.

1.1 Objectives

- 1. To study present level of Energy Consumption
- 2. To Study Electrical Consumption
- 3. To assess the various equipment/facilities from Energy efficiency aspect
- 4. To study various measures to reduce the Energy Consumption

1.2 Audit Methodology:

- 1. Study of connected load
- 2. Study of various Electrical parameters
- 3. To prepare the Report with various Encon measures with payback analysis

1.3 General Details of College

Table No-1.1: Details of college

| No | Head | Particulars Apold phot Apple |
|----|---------------------|--|
| 1 | Name of Institution | Brahma Valley College Of Engineering And Research Institute, Nashik |
| 2 | | Brahma Valley College Of Engineering And Research |
| | Address | Institute, Anjaneri, Trimbak Road, Nashik, Maharashtra 422 213. |
| 3 | Affiliation | Savitribai Phule Pune University |



| A001 | Faculty Room | 1 | | | OD MBA | 1 11 |
|------|----------------------------|----|-----|-------------|-----------------------|-----------|
| A002 | Faculty Room | 2 | | | 11del u | 1 11 |
| A003 | HOD Mechanical Engg. | | 1 | | II 1 day o | 2 |
| A004 | Board Room | 2 | | 3 | lass Koom M | 3 |
| A005 | RAC Lab. | 6 | | II-AE | iass Room M | 4 |
| A006 | Class Room- B.E. Mech -A | 6 | | y Lab. | ngg. Chemist | 4 |
| A007 | Thermodynamics Lab. | 9 | | 9009 | OD angg. Sc | 6 |
| A009 | Metallurgy Lab. | 6 | | .08 | ngg.Pijysics L | 2 |
| A010 | Turbo Machines Lab. | 4 | | | moly kin | 2 * |
| A012 | Fluid Mechanics Lab. | 8 | 5 | A- 3 | lass Room F. | 4 |
| A013 | BME Lab. | 5 | | 21-10 | 2 | 3 |
| A014 | MQC Lab. | 8 | . 1 | tingg. | OD biccinoa | 4 |
| A103 | Heat Transfer Lab. | 8 | | | MI Lab. | 4 |
| A104 | Dynamics of Machinery Lab. | 10 | | | ower System | 1 018 |
| A104 | Theory of Machines Lab. | 10 | | ics Lab. | 2 | 4 |
| A105 | Fluid Power Lab. | 8 | | .68.1 | ontrol System | 1 1018 |
| A105 | Mechatronics Lab. | 8 | 5 | unes Lab. | ioctrical Maci | 3 |
| A207 | Tutorial Room | | | 8 | igh voltage | F 7119 |
| A207 | Class Room B.E. MechB | | - | 8 | omputer Lab. | 5 FIIR |
| A209 | Class Room S.E. MechA | | | 8 | iass koom 5. |) 607FF |
| A210 | Class Room S.E. MechB | | | 4 | iass Room 1. |) 0179 |
| A211 | Class Room T.E. MechA | | | 4 | Eass Koopt B. | 7 1178 |
| A212 | Class Room T.E. MechB | | | 4 | nd IIVIO (10) | 1 TOWN |
| B207 | Drawing Hall-I | | | 4 | nvironmentai | F .7009 |
| B208 | Drawing Hall-II | | | 4 | trength of Ma | \$ NOOR |
| 101A | Project Lab. | | | lology Lab. | onerete Lechi | €008 |
| 101B | Programming LabII | | | | urvey Lab. | S austi |
| 106 | Computer Center | | 2 | 29 | 60 | 7 |
| A106 | Programming LabI | 8 | | ngg, Lab. | 16 | 3 |
| A107 | Hardware Lab. | 6 | | bngg Lab. | ransportation | 3 |
| A108 | HOD Computer Engg. | 2 | | .da.1 20 | ngg. hicknan | 1 |
| A109 | Software LabI | 4 | | Leb. | 10 | 2 |
| A110 | Software LabII | | | E. CIVIL | jass Koom 5. | 7 +60791 |
| A111 | Database Lab. | 2 | | 1171-7-21 | 18 | 1/28 |
| A204 | Class Room S.E. Comp. | | 8 | E. CIVIL | lass koom b. | 3 |
| A205 | Class Room T.E. Comp. | | 4 | (10017-0) | mouch agrees | 1 |
| A206 | Class Room B.E. Comp. | | 4 | 13001 | 16114) 95 1860 | |
| A208 | Tutorial Room | | | . (300FL) | MOD'S SPRING | A. |
| B008 | Language Lab. | | | (1001) | assauc (Fust | I A |

Report on Energy Audit: Brahma Valley College Of Engineering And Research Institute, Nashik

| A | Passage (Second Floor) | nollq | Consum | 10 | d Electrical | 3. Study o |
|-----------|------------------------|-----------|----------|---------------|--------------|------------|
| В | Passage (Ground Floor) | 8 | 3 | | | |
| В | Passage (First Floor) | 3 | 7 | Samuel marger | Jazgana sus | 0.19 |
| В | Passage (Second Floor) | f Enginer | ollege O | 16 | n. The Brahm | oliqmuznot |
| rof reter | Total | 215 | 140 | 292 | 260 | 181 |

Apart from above load, the college has pumps, street lights. Individual fitting wise load is as under.

Table No 2.2: Equipment wise Connected Load

| No | Equipment | Qty | Load, W/Unit | Load, kW |
|----|------------------------|---------|-----------------|-------------|
| 1 | F T L-40 W | 215 | 40 | 8.6 |
| 2 | LED Tube-20W | 140 | 20 | 2.8 |
| 3 | LED bulb | 292 | 12 | 3.5 |
| 4 | Computers | 260 | 65 | 16.9 |
| 5 | Ceiling Fan | 181 | 65 | 11.8 |
| 6 | LED focus Street light | 20 | 35 | 0.7 |
| 8 | Pumps (5HP) | | | 3.7 |
| | Total | PI-JUKI | | 16.2 |

Data can be represented in terms of PIE chart as under,




Figure 2.1: Distribution of connected load.






Figure 3.1: Month wise energy consumption

Monthly variation in electricity bill is as follows,




Figure 3.2: Month wise electricity bill



4. Carbon Foot printing

1. A Carbon Foot print is defined as the Total Greenhouse Gas emissions (CO₂ emissions), emitted due to various activities. In this we compute the emissions of Carbon-Di-Oxide, by usage of the various form of Electrical Energy used by the College for performing its day to day activities

2. Basis for computation of CO2 Emissions:

The basis of Calculation for CO₂ emissions due to Electrical Energy is as under

➤ 1 Unit (kWh) of Electrical Energy releases 0.8 Kg of CO₂ into atmosphere.

Based on the above Data we compute the CO₂ emissions which are being released in to the atmosphere by the College due to its Day to Day operations

The Brahma Valley College Of Engineering And Research Institute, Nashik is situated in Brahma Valley Educational Campus. Entire Campus is having single energy meter for all institutes situated in campus. CO₂ emissions due to Electrical Energy is calculated for entire campus.

We herewith furnish the details of various forms of Energy consumption as under



5. Study of utilities

5.1 Study of Lighting

In the facility, the lighting system can be divided mainly in to parts, indoor lighting and outdoor lighting. There are 215 FTL fittings with Electronic/ magnetic chokes, 292 nos of LED tubes, 140 nos of LED bulbs. It is recommended to install the 20 W LED Tube light fittings in place of these old T-8 fittings. There are 30 No of LED street lights.

5.2 Ceiling Fans

At building facility, there are about 181 Nos Old Ceiling Fans, which consumed about 65 W of Electrical Energy. It is recommended to replace these old Fans with BEE STAR Rated Ceiling Fans.

5.3 Water Pumps

There are in total 1 Water pumps with 5HP.



7. Study of usage of LED lighting

In this chapter we study the lighting system of college and compute the percentage of total load catered by LED lighting.

Table 7.1: Total lighting load

| No | Particulars | Qty | Load, W/Unit | Load, |
|--------|--------------------------|---------|-----------------|-------|
| 100 | FT L-40 W | 215 | 40 | 8.6 |
| 2 | LED lighting load | -Tfo | resent Qu | |
| 1 111 | LED tube | 140 | 20 | 2.8 |
| 2 | LED bulbs | 292 | 12 | 3.5 |
| 3 | LED street lights | 20 | 35 | 0.7 |
| yeG\s | Total LED lighting loadl | giy Çiy | g sgmav/ | 7.0 |
| /h/Day | Total Lighting load | H m 2 | avas yliaC | 15.6 |

It can be seen that out of total lighting load 45% load is LED lighting load.



8.2 Replacement of old fans with STAR Rated fans

During the Audit, it was observed that there are 181 no of fans. It is recommended to replace these old fans with STAR Rated fans.

In the following Table, we present the savings, investment required & payback analysis.

| No | Particulars | Value | Unit |
|--------|---|----------|-----------|
| 1 | Present Qty of Old Ceiling Fan fittings | 181 | Nos |
| estatu | Energy Demand of Old Ceiling Fan | REPORTED | BIHERY P |
| 2 | fitting | 65 | W/Unit |
| 3 | Energy Demand of STAR Rated Fan | 52 | W/Unit |
| 4 | Reduction in demad | 13 | W/Unit |
| 5 | Average Daily Usage period | 4 | Hrs/Day |
| 6 | Daily saving in Energy | 9.412 | kWh/Day |
| 7 | Annual Working Days | 250 | Nos |
| 8 | Annual Energy Saving possible | 2353 | kWh/Annum |
| 9 | Rate of Electrical Energy | 11 | Rs/kWh |
| 10 | Annual Monetary saving | 25883 | Rs/Annum |
| 11 | Cost of STAR Rated Ceiling Fan | 2174 | Rs/unit |
| | | | Rs lump |
| 12 | Investment required | 393494 | sum |
| 13 | Simple Payback period | 182 | Months |



8.4 Summary of Savings

| No | Recommendation | Annual Saving potential, kWh/Annum | Annual Monetary Gain, Rs. | Investment Required, Rs. | Payback period, Months |
|----|---|------------------------------------|---------------------------------|--------------------------------|------------------------------|
| 1 | Replacement of 215 Nos T-8 fittings with 20W LED fittings | 4,300 | 47,300 | 137,815 | 35 |
| 2 | Replacement of 181 Nos Old Ceiling Fans with STAR rating fans | 2,353 | 25,883 | 393,494 | 182 |
| 3 | Installation of 100kW grid connected PV panel | 150,000 | 1,650,000 | 5,000,000 | 36 |
| | Total | 156,653 | 1,723,183 | 5,531,309 | 39 |

